

# PEPCO VAULT LOWERING AT 9<sup>TH</sup> & MONROE STREET



## OVERVIEW

**Location:** 9<sup>th</sup> & Monroe Street, NE  
Washington, DC

**Client:** Horning Brothers Inc.

**Period of Performance:**  
June 2017—August 2017

**Contract Value:** \$22,535.71

**FMCC Job No.:** 10455

## Project Description

The PEPCO Vault Lowering project was an emergency project subcontracted to Fort Myer Construction by Horning Brothers to lower the side walls of a PEPCO Vault on the northeast corner of Monroe Street and 9<sup>th</sup> Street.

Fort Myer's responsibilities included excavating a manhole 24" below proposed grade, saw cutting existing concrete manhole 12" below grade, removal of excess manhole walls, frame, and cover. We also performed installation of a new frame and cover level with the new proposed grade, along with back fill of the manhole and final restoration of the sidewalk.

## Project Significance

This project shows our electrical department's ability to handle emergency projects in a timely manner and on budget.

## Client References

Alex Berleya, Construction Manager, Horning Brothers  
333 14<sup>th</sup> Street, NW | Washington, DC 20010  
aberley@horningbrothers.com | 202.659.0700

## Key Personnel

Mike Dorsey - Project Manager  
Travis White - Superintendent  
Stephen Sessa - Foreman

